

M-99 Road Construction

Windsor Township, Eaton County Delhi Township, Ingham County April - November 2025

What Is Being Done?

Starting this spring, the Michigan Department of Transportation (MDOT) will be completing road improvements and rebuilding on M-99 from Holt Highway to Edgewood Boulevard in Ingham and Eaton counties. The construction phase for this project is expected to be finished by November.

How Will Traffic Be Affected?

Pre-stage work includes tree clearing, temporary widening, crossover installation, and installation of storm sewer crossings. Traffic will be maintained via single-lane closures.

Stage 1: Rebuilding the northbound lanes and installing the new northbound shoulder. Traffic

will be maintained on the southbound through-lanes and center turn lane.

 Stage 2: Rebuilding the southbound lanes and installing the new southbound shoulder. Traffic will be maintained on the rebuilt northbound through-lanes and existing center turn lane.

Project limits of road improvements and rebuilding on M-99

Project Limits

- Stage 3: Rebuilding the center turn lane.
 The center turn lane along with the inside northbound and southbound through-lanes will be closed. Traffic will be maintained on the rebuilt outside northbound through-lane and outside southbound through-lane. The dedicated left-turn lanes will be open at major intersections.
- Stage 4: Placing the asphalt top course on M-99 lanes and approaches, including all permanent pavement markings. Traffic will be maintained via single-lane closures.

As part of stages 1 and 2, intersection approaches to M-99 will need to be closed for rebuilding. That approach rebuilding will occur in halves, with approaches on the east side of M-99 being built in Stage 1 and the west side approaches in Stage 2.



For More Information:

Call or email the MDOT Lansing Transportation Service Center at **517-335-3754** or MDOT-LansingTSC@Michigan.gov. For project updates, go to www.Michigan.gov/Drive.